

Addendum To

Request for Bid for Asbestos Removal & Deconstruction

Sealed Bids Will Be Received Until 12:00 p.m. (Noon) Thursday August 30, 2018

City of Earlville

Attention: Lind Gaul, City Clerk

19 Northern Avenue

Earlville, IA 52041

No bids will be received after this time.

Bids will be publicly opened and read out loud at 12:15 p.m. Thursday August 30, 2018 at the Earlville City Hall, 19 Northern Avenue, Earlville, IA.

Number 9 (on page 4): The Contractor shall obtain inspection and approval from the Project Manager prior to backfilling any excavations, holes or depressions on the site as a result of the deconstruction/demolition. Excavations, cellar holes, basement holes, abandoned cisterns or other depressions in the wrecking site shall be filled and compacted with sand or earthen fill from a previously used borrow pit. A tillable layer of topsoil (4-6 inches) from a previously used site must be spread over the entire lot to a uniform, natural grade consistent with established adjacent grades. (No fly ash or equal). The Contractor can elect to crush the clean building concrete onsite and spread over the entire lot to a uniform, natural grade consistent with established adjacent grades.